13	Providing and laying semi dense bituminous concrete 25mm thick with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder at 4.5 to 5% of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH Specification clause No. 500.8 complete in all respects as per specifications. With 80/100 grade bitumen using 40-60 HMP using Mechanical paver complete as per specifications.	Cum	54.25	9288.14	Rupees Nine Thousand Two Hundred Eighty Eight and Fourteen Paise Only	503881.60
14	Carriage of Mixed Materials complete as per specifications.	Cum	54.25	49.42	Rupees Forty Nine and Forty Two Paise Only	2681.04
15	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading complete as per specifications.	Cum	709.31	74.19	Rupees Seventy Four and Nineteen Paise Only	52623.71
					Total	1800311.50
					Percentage	-5.17%

B.T. Ramireddy

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,